GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Water Resources Department – Minor Irrigation – Nellore District – Improvement to Kolladinne Thummalapenta Tank supply channel in Kavali Mandal, Nellore District Administrative sanction for an amount of Rs.491.00 lakhs- Accorded – Orders – Issued.

WATER RESOURCES (MI.A2) DEPARTMENT

G.O.RT.No. 587 Dated: 20-08-2018

Read:

From the Chief Engineer, Minor Irrigation, Letter No.DCE-OT.2-T2/ KTS Channel System, dated 28.06.2018.

O R D E R:

In the reference read above, the Chief Engineer, Minor Irrigation, has stated that the Thummalapenta tank is having a registered ayacut of 1092 acres, and un-registered ayacut of 1500 acres in mainly dependent on inflows from KTS channel. The KTS channel received water from Dagadarthi Mungamuru channel, (DM Channel) and also rain water from Mungamuru Tank Supply channel (MTS channel). During rainy days the MTS channel receives rain water and due to insufficient carrying capacity of KTS Channel, the rain water from MTS channel could not be drawn into KTS channel and is going waster into the sea through surplus arrangements of MTS channel. The KTS channel is the tail end of the D.M channel system. The total length of KTS channel is 8.0 Km and it crossed two drains viz., Chippaleru and Kondepi drain where the canal will be in complete banking. Due to sandy soils, water is seeping through the banks in banking portion and causing breaches at several places. Hence, it is proposed to construct CC walls to canal banking portion for a length of 500m at both sides. The inspection path on KTS channel is in damaged condition and the vehicles cannot move on this path in present condition and it is very difficult to inspect the canal during water regulation period. Improvements are to be made to the jeep track by raising the banks and laying 300mm thick gravel layer on top.

2. The Chief Engineer, Minor Irrigation, while submitting the estimate for the work "Improvements to Kolladinne Thummalapenta Tank Supply Channel in Kavali Mandal, Nellore District for Rs.495.00 lakhs has requested the Government to accord administrative sanction under Head of Account "4702-00-101-11-SH(21) -530/531 OE".

3. Government after careful examination hereby accorded administrative sanction for an amount of Rs.491.00 lakhs (Rupees four hundred and ninety one lakhs only) for the work for the work Improvements to Kolladinne Thummalapenta Tank supply channel in Kavali Mandal, Nellore District, under Head of Account "4702-00-101-11-SH(21) -530/531 OE". subject to that the CE, MI may be requested to attend the following before according Technical sanction.

i) Ensure the correctness of provisions, quantities and rates proposed in the estimate and

P.t.o.,

ii) The design/drawings are to be approved by the competent authority in terms of economical section and stability of the structure.

4. The Chief Engineer, Minor Irrigation, shall take necessary action accordingly.

5. This order issues with the concurrence of Finance Department vide their U.O.No.47027/205/FMU-WR.I/2018 (Computer No.557834) dated 03.08.2018.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SHASHI BHUSHAN KUMAR
SECRETARY TO GOVERNMENT

To
The Chief Engineer, Minor Irrigation, Vijayawada.
The District Collector, Nellore District.

Copy to:

The Accountant General, A.P., Hyderabad
The Director of works Accounts, Vijayawada.
Finance (FMU.WR.I) Department
P.S to Hon'ble Minister (WR)
PS to Secretary to Govt. Water Resources Department.
Sf/Sc

//FORWARDED;;BY ORDER//

SECTION OFFICER